



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1033826
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 March 2009
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

OPERATOR: License #: 5030
 Name: Vess Oil Corporation
 Address 1: 1700 WATERFRONT PKWY BLDG 500
 Address 2: _____
 City: WICHITA State: KS Zip: 67206 + 6619
 Contact Person: W.R. Horigan
 Phone: (316) 682-1537
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E09803.26 Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 1951 Bottom: 1980 T.D. 2036
Admire Depth to Top: 593 Bottom: 603 T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15-015-19748-00-00
 Spot Description: _____
 SE NW SE NW Sec. 33 Twp. 25 S. R. 5 East West
3,377 Feet from North / South Line of Section
3,347 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Butler
 Lease Name: PIERPOINT A Well #: 101 W
 Date Well Completed: 11/21/1965
 The plugging proposal was approved on: 12/14/2009 (Date)
 by: Duane Krueger (KCC District Agent's Name)
 Plugging Commenced: 12/15/2009
 Plugging Completed: 12/15/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Kansas City	saltwater		13.375	23	0
Admire	saltwater & slight oil	surface	8.625	649	0
		production	5.5	2035	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Backside cemented 775 to surface: 3/2000. Ran tbg to 565', circulate hole full of 70 sx 60/40 Pozmix, 4% gel. Trip out, top off w/22 sx. Consolidated ticket #23147

RECEIVED
 DEC 17 2009
 KCC WICHITA

Plugging Contractor License #: 32991 Name: Simmons Well Service, Inc.
 Address 1: 6730 SE SATCHELL CRK RD Address 2: _____
 City: LEON State: KS Zip: 67074 + 7918
 Phone: (316) 745-8772
 Name of Party Responsible for Plugging Fees: Vess Oil Corporation
 State of Kansas County, Sedgwick, ss.
Casey Coats Employee of Operator or Operator on above-described well.
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature