

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5447  
Name: Oxy USA, Inc.  
Address 1: PO Box 2528  
Address 2: \_\_\_\_\_  
City: Liberal State: KS Zip: 67905  
Contact Person: Kenny Andrews  
Phone: (620) 629 4232  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENR #1 Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Morrow Depth to Top: 4686 Bottom: 4692 T.D. 6200'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API No. 18 - 189-22169-00-00  
Spot Description: C N/2 NW NW NE  
1/4 1/4 1/4 1/4 Sec. 3 Twp. 32 S. R. 39  East  West  
330 Feet from  North /  South Line of Section  
1980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Stevens  
Lease Name: MLP Younggren A 2  
Date Well Completed: 8-9-1997  
The plugging proposal was approved on: 9-2-09 (Date)  
by: Jack MacLasky (KCC District Agent's Name)  
Plugging Commenced: 9-11-09  
Plugging Completed: 9-16-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Produced Out
			8 5/8	1710	-
			5 1/2	6200	375

RECEIVED  
OCT 26 2009  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls + 25 sx cmt to plug perfs from 4686 to 4486. 5 1/2 showed stuck @ 400. Ran CBL from 1750 to 0. 5 1/2 showed partial bond from 1710 to 410. Ran 2 3/8 to 1740. Mixed 25 sx plug from 1740 to 1540. Pull 5 1/2. Ran 1" to 600. Mixed 65 sx plug 600 to 250. 10 sx 40 to 0. Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.  
Address 1: Rt 1 Box 49 BA Address 2: \_\_\_\_\_  
City: Tyrone State: OK Zip: 73951 + 9731  
Phone: (580) 854 6515  
Name of Party Responsible for Plugging Fees: Oxy USA Inc 1701 N. Kansas PO Box 2528 Liberal, KS 67905  
State of Kansas County: Seward, ss.  
Kenny Andrews (Print Name)  Employee of Operator or  Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Kenny Andrews