

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 62-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc.
Address 1: PO Box 2528
Address 2: _____
City: Liberal State: KS Zip: 67905
Contact Person: Kenny Andrews
Phone: (620) 629 4232
Type of Well: (Check one) ☐ Oil Well ☒ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENE #1 Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filled? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 5512' Bottom: 5880' T.D. 6000'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 18 - 129-20988-00-01
Spot Description: NW SW NE
NW 1/4 Sec. 4 Twp. 32 S. R. 39 ☐ East ☒ West
1650 Feet from ☒ North / ☐ South Line of Section
2310 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☒ NE ☐ NW ☐ SE ☐ SW
County: Morton
Lease Name: Israel A Well #: 6
Date Well Completed: 6-20-89
The plugging proposal was approved on: 9-17-09 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 9-18-09
Plugging Completed: 9-18-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Fulled Out
			20	40	—
			8 5/8	1723	—
			5 1/2	5999	—
					—

RECEIVED
OCT 26 2009

KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 600 lb. hulls & 25 sx cmt to plug perfs from 5512 to 5312, mud spacer to 2380, mixed 25 sx cmt. 2380 to 2160, mud spacer to 1750, 10 sx cmt. 1750 to 1650, mud to 550, 60 sx cmt. 550 to 0. Annulus was full of cmt. Cut 8 5/8 + 5 1/2 + capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1011 N. Kansas P.O. Box 2528 Liberal, KS. 67905
State of Kansas County: Seaward, ss.
Kenny Andrews ☒ Employee of Operator or ☐ Operator on above-described well.
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Kenny Andrews