

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc.
Address 1: PO Box 2528
Address 2: _____
City: Liberal State: KS Zip: 67905
Contact Person: Kenny Andrews
Phone: (620) 629 4232
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 5463 Bottom: 5465 T.D. 6000'

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 18 - 129-21122-0000
Spot Description: _____
SE-SE Sec. 33 Twp. 31 S. R. 39 East West
660 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Morton
Lease Name: Hobble A Well #: 2
Date Well Completed: 4-29-1992
The plugging proposal was approved on: 7-27-09 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 9-16-09
Plugging Completed: 9-17-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Run In
			8 5/8	1714	—
			5 1/2	5999	—

RECEIVED
OCT 26 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls & 25 sx cmt. to plug perfs from 5463 to 5263, mud spacer to 1750, then mixed 25 sx plug from 1750 to 1550, mud spacer to 600, mixed 64 sx plug 600 to 0. Annulus cmt'd to 0. Cut 8 5/8 & 5 1/2 & capped 8 5/8 4 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS, 67905
State of Kansas County: Seward, ss.
Kenny Andrews (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: [Signature]

PLST