


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham

County. Sec. 23 Twp. 10S Rge. 21 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
Lease Owner Anderson-Prichard Oil Corp.
Lease Name Pierce Well No. 3
Office Address 1000 Apco Tower Oklahoma City 2, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 19 19 51
Application for plugging filed July 19 19 51
Application for plugging approved July 19 19 51
Plugging commenced July 19 19 51
Plugging completed July 19 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. R. Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	278'	8 5/8"	278'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


3800' - 241 $\frac{1}{2}$ ' - Heavy Rotary Mud
241 $\frac{1}{2}$ ' - 240' - Wooden Plug
240' - 194' - 15 sacks cement
194' - 41 $\frac{1}{2}$ ' - Heavy Rotary Mud
41 $\frac{1}{2}$ ' - 40' - Wooden Plug
40' - 6' - 10 sacks cement
6' - Surface - Cellar

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corp.
Address 1000 Apco Tower Oklahoma City 2, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
Glenn W. Peel (employee of owner) or (~~owner or operator~~) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL
BY: [Signature]
(Signature) P. O. Box 359, Holsington, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 25th day of July, 19 51
Manan M. Herbert
Notary Public.

PLUGGING
FILE SEC 23 T 10 R 21 W
BOOK PAGE 97 LINE 10

DRILLER'S LOG

Company: Anderson-Prichard Oil Corp.

NE SE NE
Sec. 23, Twp. 10S, Rge 21W,

Farm: Pierce Well No. 3
Total Depth: 3800'

County: Graham,
Kansas

Comm: 7-9-51 Comp: 7-19-51

Contractor: Glenn W. Peel

Elevation:

Casing: 8 5/8" 278' cem.

Production: Dry

Figures below indicate bottom of formations

Surface Soil	0 -	280
Shale & Shells		570
Sand		660
Shale & Shells		1670
Anhydrite		1680
Shale		1770
Shale & Shells		2125
Shale		2275
Liem & Shale		2385
Lime		2485
Lime & Shale		3040
Lime		3120
Total Depth		3800

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN to before me this 25th day of July, 1951.

My commission expires June 4, 1955 *Marion M. Herbert*
Notary Public



PLUGGING
FILE SEC 23T 10 R 245
BOOK PAGE 97 LINE 10

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1951
CONSERVATION DIVISION
Wichita, Kansas