

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 2 TWP. 10 RGE. 21w E/W
Location as in quarters or footage from lines:
330' FWL 990' FSL NW 1/4 330' FSW 990' FWL NW 1/4

Locate Well
correctly on above
Section Platt.

Lease Owner Phillips Petroleum Co.
Lease Name Noah #4 Well No. _____
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 1/25/83
Plugging completed 2/11/83
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation _____ Depth to top _____ bottom _____ T.D. 3842'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1788'	none
				5 1/2"	3806'	2401'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged bottom with 5 sacks cement, sanded to 3450' & 5 sacks cement.
Shot pipe at 2621', 2500', & 2415'. Pulled total of 60 joints of pipe.
Plugged well with 25 sacks gel, 2 hulls, 70 sacks cement, 10 sacks gel,
plug, & 70 sacks 50/50 pos. 6% gel, & 3% c.c.
Plugging complete


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrel Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrel Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of FEBRUARY, 1983



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1983
2-22-1983
CONSERVATION DIVISION
Wichita, Kansas

Formation Record

Lease **Noah**Well No. **4**

FROM	TO	Formation	REMARKS
0	220	Surface Sand	Elevation: Grd: 2264' D.F. 2266' R.K.B. 2268'
220	1620	Sand and Shale	
1620	1790	Anhydrite	Top Anhydrite 1752'
1790	1926	Shale and Redbed	
1926	2206	Shale	
2206	2890	Line and Shale	
2890	2975	Shale	
2975	3050	Line and Shale	
3050	3134	Shale	
3134	3776	Line and Shale	Tops: Heebner 3466'; Toronto 3489' L.K.C. 3508'; Marmaton 3746'
3776	3842	Line	Top Arbuckle 3805'