

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Graham SEC. 2 TWP. 10S RGE. 21W ~~NE~~  
 Location as in quarters or footage from lines:  
 SW SW NE


Lease Owner John O. Farmer, Inc.  
 Lease Name Sutor "A" Well No. #1 (Twin)  
 Office Address P.O. Box 352, Russell, KS 67665  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed August 29, 1950  
 Application for plugging filed March 30, 1982  
 Plugging commenced 2:30 P.M., May 3, 1982  
 Plugging completed 3:45 P.M., May 3, 1982  
 Reason for abandonment of well or producing formation noncommercial

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
 Producing formation Arbuckle Depth to top 3837' bottom 3848' T.D. 3848'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	135'	
				5-1/2"	3836'	

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Down 8-5/8" casing - mixed 100 sxs. cement

Down 5-1/2" casing -- mixed 1 hull with 60 cement - 2 hulls  
with 10 gel - released plug - 100 sxs. cement

Maximum pressure - 200#

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 12 1982  
 5-12-1982  
 CONSERVATION DIVISION  
 Wichita Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor John O. Farmer, Inc.  
P.O. Box 352, Russell, KS 67665

STATE OF Kansas COUNTY OF Russell, ss.


John O. Farmer III (~~Employer or owner~~) (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer III  
P.O. Box 352, Russell, KS 67665  
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 82

Margaret A. Schulte  
 Margaret A. Schulte Notary Public.

My Commission expires: January 27, 1985



**SIDE TWO**

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Sand	0	135		
Shale	135	700		
Sand	700	775		
Shale & Shells	775	850		
Shale, Shells, & Sand	850	1400		
Shale & Shells	1400	1750		
Anhydrite	1750	1805		
Shale & Shells	1805	2260		
Lime & Shale	2260	2600		
Shale & Lime	2600	2685		
Lime & Shale	2685	3580		
Lime	3580	3848		

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (I. O. D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	2-1/4"	8-5/8"		135'	Common	100	
Production	2-1/8"	5-1/2"		3836'	Common	75	

STATE OF KANSAS  
 DEPARTMENT OF REVENUE  
 DIVISION OF OIL & GAS  
 WICHITA, KANSAS  
 4-1-1982

SUTOR "A" #1 (Twin)  
 SW SW NE Sec. 2-10S-21W  
 Graham County, Kansas