

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER (Comp.) 12-14-50

LEASE NAME V. V. White

WELL NUMBER #5

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 2 TWP. 10SRGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed 12-14-50

Plugging Commenced 6-21-88

Plugging Completed 6-27-88

RECEIVED
STATE CORPORATION COMMISSION
1-6-1989
JAN 6 1989

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco Inc. for Texaco Producing Inc.
Wichita, Kansas

ADDRESS P.O. Box 2420, Tulsa, OK 74102

PHONE# (918) 560-6000 OPERATORS LICENSE NO. 4742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 23, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lansing - KC
E&I Depth to Top 3792' Bottom 3799' T.D. 3799'

Simpson (Shut-in)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing - KC	Oil	3560'	3781'	8-5/8"	285'	None
E & I				5-1/2"	3792'	None
Simpson						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
urf. cemented from 285' to 6' w/ 50 sx w/100# hulls. Cemented from 3799' to 6' w/250 sx w/400# hulls, cut off casing at 6' below ground level, welded on steel plate, filled w/ native dirt, cleaned and leveled location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texaco Inc. for Texaco Producing Inc. License No. _____

Address P.O. Box 2420, Tulsa, OK 74102

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

John K. Hamby

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John K. Hamby

(Address) _____

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 89

Deborah M. Coburn
Notary Public

Commission Expires: 8-3-92

