


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 2 Twp. 10S Rge. (E) 21W(W)
Location as "NE/CNW/SW" or footage from lines 330' f/WL & 990' f/SL of NW/4
Lease Owner Phillips Petroleum Company
Lease Name Noah Well No. 5
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 16, 1951 19
Application for plugging filed 1-12-73 19
Application for plugging approved 1-15-73 19
Plugging commenced 1-29-73 19
Plugging completed 2-2-73 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 2-16-71 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation LKC-Toronto Depth to top 3509 Bottom 3732 Total Depth of Well 3750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Toronto	Oil-Water	3509	3519	8-5/8"	1809	None
LKC	Oil-Water	3525	3732	5-1/2"	3823	2691'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dmpd sand 3750-3500', Dmpd cmt (5 sx) 3500-3465'. Shot 5 1/2" csg @ 3011', 2819', 2710' = pulled 70 jts (2691.33') 5 1/2" OD 14# csg. Set wood bridge 1050-1035'. Dmpd rock 1035-1000'. Dmpd 7 Cu. Yds. cmt 1000-740'. MOCPU, WOC 24 hrs. Dmpd 6 yds cmt 740' to surface. Well P&A 2-2-73.

RECEIVED
STATE CORPORATION COMMISSION
2-12-1973
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. A. T. Slagle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A. T. Slagle Prod. Supt.

Box 287, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of February, 19 73

Lura Lee Parks
Notary Public.

My commission expires 10-27-73



Formation Record

Lease **Noah**Well No. **5**

FROM	TO	Formation	REMARKS
0	555	Sand & Shale	Elevation: Ground 2287'
555	965	Shale	
965	1480	Sand & Shale	
1480	1705	Shale & Pyrite	
1705	1785	Shale & Anhydrite	
1785	1810	Anhydrite	
1810	2135	Shale & Redbed	
2135	2315	Shale	
2315	3445	Lime & Shale	
3445	3500	Lime	Top Heebner 3485'
3500	3540	Lime & Shale	Tops: Toronto 3505'; LKO 3524'
3540	3617	Lime	
3617	3825	Lime & Shale	Top Arbuckle 3825'
3825	3840	Lime	

RECEIVED
STATE CORPORATION COMMISSION
2-12-1973
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas