


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 2 Twp. 10 Rge. 21W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW NW  
Lease Owner Phillips Petroleum Company  
Lease Name Noah Well No. 1  
Office Address Box 287, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 13, 1950 19  
Application for plugging filed March 5, 1969 19  
Application for plugging approved March 6, 1969 19  
Plugging commenced March 27, 1969 19  
Plugging completed April 2, 1969 19  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 17, 1964 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols PRTD 3770  
Producing formation Arbuckle Depth to top 3819' Bottom 3833' Total Depth of Well 3833 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil-Water	3819	3833	8-5/8"	1796'	
LKC	Oil-Water	3509	3736	5-1/2"	3845'	2504'
Toronto	Oil-Water	3492	3504			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

CIBP @ 3770'. Knight CPU pushed 5 1/2" wood plug to 3450', Dmpd 60 gals sand 3450-3400', 5 sx cmt 3400-3365'. Shot 5 1/2" csg @ 2600' & 2504' - pulled 80 jts (2504') of 5 1/2" csg. Mudded hole 3365-1600', 35 sx Jel mud 1600-200', 60 sx cmt 200' to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

A. T. Slagle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle Dist. Supt.

Box 287, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of April, 1969

My commission expires 10-27-69  
Lura Lee Jacobs  
Notary Public.

## Formation Record

Lease Noah

Well No. 1

FROM	TO	Formation	REMARKS
0	191	Sand.	Elevation: 2269 RKB
191	735	Surface Clay.	
735	1151	Shale, Shells and Sand.	
1151	1259	Shale, Shells and Pyrite.	
1259	1478	Sand, Shale and Redbed.	
1478	1523	Shale and Redbed.	
1523	1725	Shells and Redbed.	
1725	1790	Anhydrite and Redbed.	
1790	1791	Redbed.	
1791	2179	Redbed and Shale.	
2179	2322	Shale.	
2322	2350	Shale and Sand.	
2350	2354	Shale.	
2354	2868	Lime and Shale.	
2868	2900	Shale.	
2900	2952	Lime and Shale.	
2952	3037	Shale and Shells.	
3037	3103	Shale.	
3103	3490	Lime and Shale.	
3490	3528	Lime.	
3528	3713	Lime and Shale.	
3713	3731	Lime.	
3731	3833	Lime and Shale.	

RECEIVED  
STATE CORPORATION COMMISSION  
4-9-1969  
APR 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Tops: Howard 3254' - Topeka 3284' -  
Heebner 3466'.  
Tops: Toronto 3493' - L.K.C. 3510'.

Tops: Arbuckle 3819'.