

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

12/27/09

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 33344
Name: Quest Cherokee, LLC
Address: 211 W. 14th Street
City/State/Zip: Chanute, KS 66720
Purchaser: Bluestem Pipeline, LLC
Operator Contact Person: Jennifer R. Ammann
Phone: (620) 431-9500
Contractor: Name: TXD Drilling
License: 33837
Wellsite Geologist: Ken Recoy

CONFIDENTIAL
DEC 27 2007
KCC

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

9/4/07	9/6/07	9/6/07
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 133-26934-0000

County: Neosho

Sec. 1 Twp. 19 S. R. 19 East West

560 feet from S / N (circle one) Line of Section

1880 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name: Daniels Rev. Trust Well #: 1-2

Field Name: Cherokee Basin CBM

Producing Formation: multiple

Elevation: Ground: 945 Kelly Bushing: n/a

Total Depth: 963 Plug Back Total Depth: 947.54

Amount of Surface Pipe Set and Cemented at 22 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 947.54

feet depth to Surface w/ 128 sx cmt.

Drilling Fluid Management Plan MHJMS 5509
(Data must be collected from the Reserve Pit)

Chloride content _____ ppm Fluid volume _____ bbls

Dewatering method used _____

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jennifer R. Ammann

Title: New Well Development Coordinator Date: 12/25/07

Subscribed and sworn to before me this 25th day of December,

2007.

Notary Public: Terra Klauman

Date Commission Expires: 8-4-2010

KCC Office Use ONLY

Letter of Confidentiality Received

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 28 2007

TERRA KLAUMAN
Notary Public - State of Kansas
My Appt. Expires 8-4-2010

CONSERVATION DIVISION
WICHITA, KS

Operator Name: Quest Cherokee, LLC Lease Name: Daniels Rev. Trust Well #: 1-2
 Sec. 1 Twp. 19 S. R. 19 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Compensated Density Neutron Log Dual Induction Log Gamma Ray Neutron Log	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See attached
--	--

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8"	22	22	"A"	5	
Production	6-3/4	4-1/2	10.5	947.54	"A"	128	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	858-861/803-805/797-799	500gal 15%HCLw/ 38 bbls 2%kcl water, 500bbls water w/ 2% KCL, Blockde, 10500# 20/40 sand	858-861/803-805 797-799
4	702-704/652-654/593-595/560-563	400gal 15%HCLw/ 62 bbls 2%kcl water, 500bbls water w/ 2% KCL, Blockde, 10500# 20/40 sand	702-704/652-654 593-595/560-563
4	455-459/444-448	300gal 15%HCLw/ 54 bbls 2%kcl water, 500bbls water w/ 2% KCL, Blockde, 10500# 20/40 sand	455-459/444-448

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-3/8"	899.10'	n/a	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. 10/30/07			Producing Method		
			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	n/a	12mcf	92.4bbls		

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled

Production Interval Other (Specify) _____



QUEST

Resource Corporation

211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

CONFIDENTIAL
DEC 27 2007
KCC

TICKET NUMBER 2399

FIELD TICKET REF # _____

FOREMAN Joe

621610

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-6-07	DANIELS Rev. TRUST 1-2	1	28	19	NO

FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE
Joe	3:00	6:15		903427		3.25	<i>Joe</i>
MAVERICK	↓	5:15		903197		2.25	<i>Maverick</i>
Tyler		5:45		903600		2.75	<i>Tyler</i>
Tim	↓	6:15		931385	931387	3.25	<i>Tim</i>
Daniel	↓	5:30 6:30		931420		3.5	<i>Daniel</i>

JOB TYPE Long string HOLE SIZE 6 3/4 HOLE DEPTH 963 CASING SIZE & WEIGHT 4 1/2 10.5
 CASING DEPTH 947.54 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 0
 DISPLACEMENT 15.11 DISPLACEMENT PSI _____ MIX PSI _____ RATE 4bpm

REMARKS:

INSTALLED Cement head BAN 1 SK gel & 9 bbl dye & 128 SKS of cement to get dye to surface. flush pump. Pump wiper plug to bottom of set float shoe

947.54	ft 4 1/2 Casing
5	Centralizers
1	4 1/2 float shoe

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
903427	3.25 hr	Foreman Pickup	
903197	2.25 hr	Cement Pump Truck	
903600	2.75 hr	Bulk Truck	
1104	118 SK	Portland Cement	
1124	2	50/50 POZ-Blend Cement	
1126	1	OWC-Blend Cement	
1110	13 SK	Gilsonite	
1107	1.5 SK	Flo-Seal	
1118	1 SK	Premium Gel	
1215A	load	KCL	
1111B	3 SK	Sodium Silicate	
1123	7000 gal	City Water	
903385	3.25 hr	Transport Truck	
931387	3.25 hr	Transport Trailer	
931420	3.5 hr	80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 28 2007

CONSERVATION DIVISION
WICHITA, KS