

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 6039  
Name: L.D. Drilling, Inc.  
Address 1: 7 SW 26th Avenue  
Address 2: \_\_\_\_\_  
City: Great Bend State: Ks. Zip: 67530 + \_\_\_\_\_  
Contact Person: \_\_\_\_\_  
Phone: (620) 793-3051  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)

API No. 15 - 185-22193-00-00  
Spot Description: 100' North N/2 NW SW SW  
Sec. 18 Twp. 22 S. R. 11  East  West  
1,090 Feet from  North /  South Line of Section  
4,950 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Stafford  
Lease Name: Ross Well #: 2  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Richard Lacey (KCC District Agent's Name)

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Plugging Commenced: 10-22-09  
Plugging Completed: 10-26-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	344'	None
			5-1/2"	3649'	2380'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3500' and 5 sacks cement. Cut casing loose @2380', pulled up to 600'. pumped 10 sxs. gel and 50 sxs. cement, pulled up to 370'. pumped 50 sxs. cement, pulled up to 40' and circulated 20 sacks cement to surface. 60/40 pos, 4% gel. Plugging Complete.

RECEIVED  
NOV 02 2009

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.  
Address 1: P.O. Box 467 Address 2: \_\_\_\_\_  
City: Chase State: Kansas Zip: 67524 + 0467  
Phone: (620) 938-2943  
Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.

KCC WICHITA

State of Kansas County, Rice, ss.  
Mike Kelso (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Mike Kelso

*[Handwritten signature]*