

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5030
Name: Vess Oil Corporation
Address 1: 1700 Waterfront Parkway
Address 2: Building 500
City: Wichita State: Ks. Zip: 67206 + _____
Contact Person: Casey Coats
Phone: (316) 215-1573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API No. 15 - 097-20861-0000
Spot Description: C-SE-NW
_____ Sec. 26 Twp. 30 S. R. 18 East West
3,300 Feet from North / South Line of Section
3,300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: Alton Unruh Well #: 3
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Jerry Stapelton (KCC District Agent's Name)

Depth to Top: _____ Bottom: 5 D
_____ Depth to Top: _____ Bottom: _____ T.D.
_____ Depth to Top: _____ Bottom: _____ T.D.

Plugging Commenced: 10-12-09
Plugging Completed: 10-16-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	528'	None
			5-1/2"	5057'	3232'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 4810' and 5 sxs. cement. Cut casing loose @3232', pulled up to 1210". pumped 15 sxs. gel and 50 sxs. cement, pulled up to 540', pumped 50 sxs. cement, pulled up to 40' and circulated 20 sxs. cement to surface. 60/40 pos, 4% gel. Plugging Complete.

RECEIVED
NOV 02 2009
KCC WICHITA

Plugging Contractor License #: 31529 Name: Mike's Teting & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Rice, ss.
Mike Kelso
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Mike Kelso