

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

19044-0000

OPERATOR: License #: 5363
Name: Berexco, Inc.
Address 1: P.O. Box 723
Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 +
Contact Person: Dennis Kirmer
Phone: (785) 628-6101
Type of Well: (Check one) Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API No. 15 - 167-05267
Spot Description: _____
SW NW NE Sec. 15 Twp. 14 S. R. 14 East West
4,290 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Boxberger Well #: A-1
Date Well Completed: 5-14-45
The plugging proposal was approved on: 9-11-09 (Date)
by: Ray Dinkel (KCC District Agent's Name)

<u>Platts</u>	Depth to Top: <u>2882'</u>	Bottom: <u>2896'</u>	T.D. _____
<u>L-KC</u>	Depth to Top: <u>3001'</u>	Bottom: <u>3100'</u>	T.D. _____
<u>Gorham Sand</u>	Depth to Top: <u>3265'</u>	Bottom: <u>3266'</u>	T.D. _____

Plugging Commenced: 9-11-09
Plugging Completed: 9-11-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Platts</u>	<u>Oil/Water</u>	<u>Surface</u>	<u>8 5/8</u>	<u>505'</u>	RECEIVED NOV 02 2009 KCC WICHITA
<u>L-KC</u>	<u>Oil/Water</u>	<u>Production</u>	<u>5 1/2</u>	<u>3265'</u>	
<u>Gorham</u>	<u>Oil/Water</u>				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 2 holes each @1450', 835', 480'. Run open end tbg to 2963'. Mix 6 sxs gel followed by 100 sxs 60/40 poz 4% gel and 300# hulls. Pull tbg to 1514'. Mix 150 sxs cement w/300# hulls. Circ good cement to surface in 5 1/2. Pull tbg out of hole. Hook to 5 1/2 csg. Mix 20 sxs cement - pressure to 300 PSIG. Hook to 8 5/8 surface pipe. Pressured to 500# - did not mix cement. Plugging done 2:30 p.m. Witnessed by Ray Dinkel, KCC Hays.

Plugging Contractor License #: 05363 Name: Berexco, Inc.
Address 1: P.O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, Inc.

State of Kansas County, Sedgwick, ss.
Dennis Kirmer Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

[Handwritten signature]