

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5363  
Name: Berexco, Inc.  
Address 1: P.O. Box 723  
Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Dennis Kirmer  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: E-07607.17  Gas Storage Permit #: \_\_\_\_\_  
Is ACC-1 filled?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L-KC Depth to Top: 3062' Bottom: 3140' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-22667-00-01  
Spot Description: \_\_\_\_\_  
C NE SW SE Sec. 17 Twp. 15 S. R. 13  East  West  
990 1009 Feet from  North /  South Line of Section  
1650 1730 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Tom Sellens Well #: 12  
Date Well Completed: 10-7-85  
The plugging proposal was approved on: 3-3-09 (Date)  
by: Ray Dinkel (KCC District Agent's Name)  
Plugging Commenced: 3-2-09  
Plugging Completed: 3-3-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L-KC	Oil/Water	Surface	8 5/8	853'	RECEIVED NOV 02 2009 KCC WICHITA
		Production	5 1/2	3389	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech, shoot 2 holes @ 1450' and 2 @ 830'. Run 2 3/8 tbg open-ended to 3190.92', spot 50 sx w/250# hulls. Pull to 2705 spot 13 sx gel. Pull to 1471' spot 50 sx, 200# hulls, pull to 1025', mix 300 sx, circ to surface 5 1/2. Pull tbg put swedge in casing, mix 70 sx circ up surface casing, shut in. Done 2:00 p.m., witnessed by Ray Dinkel KCC, Hays. (Cement used 60/40 pos 4% gel)

Plugging Contractor License #: 05363 Name: Berexco, Inc.  
Address 1: P.O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, Inc.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer