

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32466 32979 KCCPRT  
Name: Dunne Equities Operating, Inc.  
Address 1: 2200 East 22nd Street North #1100  
Address 2: \_\_\_\_\_  
City: Wichita State: Ks Zip: 67226 + 22311  
Contact Person: Gary Larue  
Phone: (316) 651-6023  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Viola Depth to Top: 2478' Bottom: 2480' T.D. 2560'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-23313 - 00-00  
Spot Description: SW1/4 NW1/4 W12 NW1/4 R12 SW1/4  
Sec. 21 Twp. 26 S. R. 5  East  West  
1320 3965 Feet from 7 North  South Line of Section  
410 4881 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: East Koogler Well #: E-3  
Date Well Completed: 2/13/1993  
The plugging proposal was approved on: 8/13/2009 (Date)  
by: Dwayne Kruger (KCC District Agent's Name)  
Plugging Commenced: 8/13/2009  
Plugging Completed: 8/13/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Kansas City 1980'-2008'	Salt Water	Surface CSG	8 5/8"	200'	0'
Viola 2478'-2492'	Oil & Salt Water	Production CSG	4 1/2"	2578'	0'
Simpson 2408'-2579'	Salt Water				
Arbucle 2577'-2579'	Salt Water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/ TBG to 2471'. Pumped 40 sacks of class A cement w/ 4% calcium. Cement plug from 2471' to 1888'. TOOH w/ TBG. RIH w/ wire line, shoot off production CSG @ 280', POOH w/ wire line. Pump 100 sacks of class A cement w/ 4% calcium down production CSG back to surface.

Plugging Contractor License #: 5870 Name: Phillips Well Service  
Address 1: P.O. Box 1263 Address 2: \_\_\_\_\_  
City: El Dorado State: Kansas Zip: 67042 + \_\_\_\_\_  
Phone: (316) 323-2160  
Name of Party Responsible for Plugging Fees: Dunne Equities Operating, Inc  
State of Kansas County, Sedwick, ss.  
Curt Ross  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
NOV 05 2009  
KCC WICHITA