

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-073-01039-00-00  
se-ne-se Sec/Twp/Rge 7-22-10 e  
1650' feet from south section line  
330' feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5387  
Operator: aztec oil co.  
Name & 625 s. main  
Address eldorado,ks. 67042  
AB oil well xxxxxxx Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

Lease/Well# pixlee 'c' #8  
County greenwood  
Well Total Depth 2454' feet  
Production Pipe: 5.5" Size Feet 2434'  
Surface Casing: 8 5/8" Size Feet 100'  
D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_ 34059

Plugging Contractor: hurricane ser. Lic. # 32006

Address: \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 2 Month: \_\_\_\_\_ 9 2008

Plugging proposal received from: \_\_\_\_\_

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: 50' cement plug @ 2400' 50' cement plug @ 1000' 250' cement plug to surface.

Plugging Proposal Received by: mike heffern

Plugging attended by Agent: All xxxxxxx Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 5 Month: \_\_\_\_\_ 1 2009

Actual Plugging Report: ran tubing to 2437' pumped 20 sxs cement, shot casing @ 800' & 252'  
ran tubing to 800' pumped 20 sxs cement, pulled tubing out, pumped 153 sxs cement to surface, pulled  
252' of 5.5" casing out, gel spacers between cement plugs.

RECEIVED

JUL 09 2009

KCC WICHITA

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I observe this plugging.

Signed:

Mike Heffern  
TECHNICIAN