

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-073-01091-00-00
^{nw} ~~sw~~ ne ne Sec/Twp/Rge 7=22=10 e
4950' feet from south section line
990' feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5387

Lease/Well# pixlee c #10

Operator: aztec oil co.

County greenwood

Name & 625 s. main

Well Total Depth 2460' feet

Address eldorado,ks. 67042

Production Pipe: 7" Size Feet 2460'

Surface Casing: 10 3/4" Size Feet 108'

AB oil well xxxxxxx Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: hurricane ser. Lic. # 32006

34059

Address: p.o. box 782228 wichita , ks.67278

Company to plug at: Hour: _____ Day: _____ 4 Month: _____ 9 2009

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: 50' cement plug @ 2400" 50' cement plug @ 1000' 250' cement plug to surface.

Plugging Proposal Received by: mike heffern

Plugging attended by Agent: All xxxxxxx Part _____
TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: _____ 29 Month: _____ 12 2009

Actual Plugging Report: ran tubing to 2443' pumped 20 sxs cement, shot casing @ 800' & 250'
pumped 20 sxs cement @ 800' pulled tubing to 250' pumped 53 sxs cement to surface, gel spacers
between cement plugs.

RECEIVED

JUL 0 9 2009

KCC WICHITA

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I observe this plugging.

Signed: *Mike Heffern*
TECHNICIAN

PH