

TALLGRASS PRAIRIE NATIONAL PRESERVE

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20705-00-00
Spot: SESWSW Sec/Twnshp/Rge: 18-18S-8E
615 feet from S Section Line, 4294 feet from E Section Line
Lease Name: DAVIS TRUST Well #: 5
County: CHASE Total Vertical Depth: 1507 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	160		70 SXS CMT
PROD	4.5	540		100 SXS CMT

Well Type: GAS UIC Docket No: Date/Time to Plug:
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: KCC Company: Phone:

Proposed Plugging Method: AS PER KCC

Control #: 20090061005 (Per Ab well Database)

Plugging Proposal Received By: Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2009 11:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

8/20 KW MOVED ON TO LOCATION AND STARTED DIGGING OUT WELL HEAD.
8/21 KW FINISHED DIGGING OUT WELL HEAD AND RIGGED UP AND KILLED WELL. KW RAN 1" DOWN CASING TO 520'. TRIED WASHING DOWN FURTHER SOLID BOTTOM. KW THEN WASHED 1/2" TUBING DOWN BACKSIDE TO 35'. THEY COULD NOT GET ANY DEEPER. W & W CIRCULATED CEMENT FROM 520' TO SURFACE INSIDE THE CASING AND CIRCULATED CEMENT FROM THE SURFACE 35' UP THE BACKSIDE. KW PULLED TUBING, AND W&W TOPPED OFF WELL WITH CEMENT. WE FINISHED AT 11:30 AM AND USED APPROX 55 SX OF COMMON.

Perfs:


Top	Bot	Thru	Comments
463	469	CSG	

RECEIVED
DEC 29 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)