

TALLGRASS PRAIRIE NATIONAL PRESERVE

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20706-00-00  
Spot: NW Sec/Twnshp/Rge: 6-19S-8E  
4335 feet from S Section Line, 7501 feet from E Section Line  
Lease Name: DAVIS TRUST Well #: 6  
County: CHASE Total Vertical Depth: 1679 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	150		70 SXS CMT
PROD	4.5	1678		155 SXS CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.  
Proposal Rcvd. from: KCC Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC

Control #: 200910061025 (Per Ab. well)

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2009 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/6 KW MOVED ON TO LOCATION AND KILLED WELL WITH 40 BBL OF WATER. KW THEN RAN 1" TUBING DOWN INSIDE OF 4 1/2" CASING TO 600' WELL BELOW THE PRODUCING ZONE. KW THEN WASHED 1/2" TUBING DOWN THE BACKSIDE TO 90' SOLID BOTTOM. W&W CIRCULATED CEMENT UP THE 4 1/2" CASING FROM 600' TO SURFACE, AND UP THE BACKSIDE FROM 90' TO SURFACE. KW PULLED THE TUBING, AND W&W TOPPED OFF THE WELL. USED APPROX 75 SXS COMMON CEMENT.

Perfs:

4 SPS 418 - 428  
4 SPS 1601 - 1606  
PER ACO-1  
PLUG SET @ 1570'

RECEIVED  
DEC 29 2009  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)