

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20680-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 19-18S-8E
2392 feet from S Section Line, 2294 feet from E Section Line
Lease Name: HATCHER Well #: 1
County: CHASE Total Vertical Depth: 1522 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		161		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: KCC Company: _____ Phone: _____

Proposed
Plugging
Method:

Control #: 20090061027 (Per Ab. Well Database, R)

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2009 2:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/12 KW KILLED WELL AND DUG OUT SURFACE CASING. SHUT DOWN FOR LUNCH. AFTER LUNCH KW CIRCULATED 1/2" TUBING DOWN THE BACK SIDE TO 10' SOLID. KW THEN RAN 1" TUBING DOWN THE 4.5" CASING TO APPROX 530' TRIED TO WASH DOWN FURTHER; SOLID BOTTOM. KW PULLED 1 JOINT. W&W CIRCULATED CEMENT FROM 525' TO SURFACE. CIRCULATED 10' TO SURFACE ON BACKSIDE. KW PULLED TUBING, AND W&W TOPPED OFF WELL. THEY FINISHED AT 2:30 PM USING 55 SXS OF COMMON. KW CUT OFF WELL HEAD AND DRESSED UP LOCATION.

NOTE: THIS WELL WAS PLUGGED AS PART OF THE
TALLGRASS PRAIRIE NATIONAL PRESERVE FEE FUND
PLUGGING PROJECT.

JK

Perfs:

RECEIVED
DEC 29 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)