

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20667-00-00

Spot: Sec/Twnshp/Rge: 18-18S-8E

3025 feet from S Section Line, 3451 feet from E Section Line

Lease Name: DAVIS TRUST

Well #: 4

County: CHASE

Total Vertical Depth: 395 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments    |
|--------|------|------------|-------------|-------------|
| SURF   | 7    | 152        |             | 81 SXS CMT  |
| PROD   | 4.5  | 540        |             | 135 SXS CMT |

Well Type: GAS

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 3097

Plug Co. Name: K W OIL WELL SERVICE, INC.

Proposal Rcvd. from: KCC

Company:

Phone:

Proposed Plugging Method: AS PER KCC

Control # 200910061004 (Per Ab Well Database)

Plugging Proposal Received By:

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/25/2009 12:00 PM

KCC Agent: SHANE JONES

Actual Plugging Report:

8/25 KW MOVED ON TO LOCATION AND KILLED WELL. KW CUT OFF SURFACE CASING. KW RAN 1" DOWN THE CASING TO 635' SOLID BOTTOM. KW PULLED 10'. KW WASHED 1/2" TUBING DOWN BACKSIDE TO 8' SOLID BOTTOM. W&W CIRCULATED CEMENT FROM 625' TO SURFACE OF CASING AND CIRCULATED CEMENT FROM 8' UP THE BACKSIDE OF THE CASING. KW PULLED THE TUBING AND W&W TOPPED OFF THE WELL. USED APPROX 55 SXS OF COMMON.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 520 | 526 | CSG  |          |

Remarks: PLUGGED DUE TO COMPLIANCE ISSUES

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

RECEIVED

DEC 24 2009

KCC WICHITA