

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20586-00-01
Spot: Sec/Twnshp/Rge: 18-18S-8E
1908 feet from S Section Line, 4604 feet from E Section Line
Lease Name: DAVIS TRUST Well #: 3
County: CHASE Total Vertical Depth: 2529 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	152		
PROD	4.5	627		

Well Type: GAS UIC Docket No: Date/Time to Plug:
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE. INC.
Proposal Rcvd. from: KCC Company: Phone:

Proposed Plugging Method: AS PER KCC
Control # 20090061003 (Per AbWell Database)

Plugging Proposal Received By: WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2009 11:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:

8/25 KW MOVED ON TO LOCATION AND KILLED WELL. KW CUT OFF SURFACE CASING HEAD. KW RAN 1" DOWN THE 4.5" CASING TO 620' SOLID BOTTOM. KW PULLED 1 JOINT OF 1". KW WASHED 1/2" TUBING DOWN BACKSIDE TO 135' SOLID BOTTOM. SHUT DOWN @ 4:30 PM. 8/26 W&W CIRCULATED CEMENT FROM 600' TO SURFACE OF CASING AND CIRCULATED CEMENT FROM 135' UP THE BACKSIDE OF THE CASING. KW PULLED THE TUBING AND W&W TOPPED OFF THE WELL. USED APPROX 66SXS OF COMMON. KW DRESSED UP LOCATION INCLUDING CLOSING IN OLD WORK OVER PIT THAT WAS ON LOCATION.

Perfs:

Top	Bot	Thru	Comments
483	485	CSG	
443	447	CSG	
433	439	CSG	

Remarks: PBTD 628' PLUGGED DUE TO COMPLIANCE

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
DEC 24 2009
KCC WICHITA