

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20584-00-01  
Spot: SW Sec/Twnshp/Rge: 18-18S-8E  
3031 feet from S Section Line, 11093 feet from E Section Line  
Lease Name: DAVIS TRUST Well #: 2  
County: CHASE Total Vertical Depth: 1580 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	150		
PROD	4.5	625		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.  
Proposal Rcvd. from: KCC Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC  
Control # 20090061002 (Per Ab. Well Database)

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/02/2009 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

9/1 KW MOVED ON TO LOCATION AND KILLED WELL. KW PERFORATED THE 2 7/8" TUBING @ 200'. W & W TRIED TO CIRCUALTE WATER AROUND BACKSIDE OF 2 7/8" TUBING NO LUCK. KW PERFORATED THE 2 7/8" TUBING @ 100'. W & W ABLE TO CIRCULATE FLUID UP THE BACKSIDE OF 2 7/8" TUBING. K W DUG OUT SURFACE HEAD AND CUT IT OFF. K W RAN 1" DOWN THE 2 7/8" TUBING 800' DID NOT TAG ANYTHING. KW WASHED 1/2" TUBING DOWN BETWEEN THE 4.5" AND 8 5/8" CASING TO 60' COULD NOT GET ANY DEEPER. I SPOKE TO JEFF KLOCK ABOUT NOT TAGGING AND THAT WELL MAYBE OPEN ALL THE WAY TO THE LANSING. JEFF SAID TO GO AHEAD AND PUMP CEMENT FROM 800'. W & W CIRCULATED CEMENT FROM 800'. AT 108 SX STARTED TO GET CEMENT COLORED WATER. WE CONTINUED PUMPING ANOTHER 12 SX DID NOT GET ANY GOOD CEMENT TO SURFACE. W & W TIED ON TO THE 1/2" TUBING AND CIRCULATED 12 SX OF COMMON UP BETWEEN THE 4 1/2" AND 8 5/8" CASINGS. K W PULLED TUBING. I HAD THEM STOP AT 100' AND CIRCULATE WATER AROUND AND UP THE BACKSIDE OF THE 2 7/8" TUBING SO THE PERFS @ 100' WOULD STILL BE OPEN TOMORROW. W & W GOING AFTER MORE CEMENT WILL TAG AND FINISH PLUGGING TOMORROW. 9/2 K W RAN TUBING IN TAGGED @ 250'. W&W CIRCULATED CEMENT TO SURFACE AND UP THE BACKISDE OF THE TUBING. KW PULLED THE TUBING AND W & W TOPPED OF THE WELL. USED 156 SXS COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
555	560	CSG	
522	526	CSG	
496	506	CSG	

Remarks: PLUGGED DUE TO COMPLIANCE YES

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

DEC 24 2009

KCC WICHITA