

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20583-00-00  
Spot: NENESW Sec/Twnshp/Rge: 19-18S-8E  
2311 feet from S Section Line, 2963 feet from E Section Line  
Lease Name: DAVIS TRUST Well #: 1  
County: CHASE Total Vertical Depth: 2730 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	150		105 SXS CMT
PROD	4.5	626		160 SXS CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.  
Proposal Rcvd. from: KCC Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC  
Control #: 2009001013 (Per Ab Well Database)

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2009 3:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/11 KW KILLED WELL AND DUG OUT SURFACE CASING. THEY FOUND CEMENT APPROX 1' DOWN ON THE BACKSIDE OF 4.5" CASING. 8/12 KW RAN 1" TUBING DOWN THE INSIDE OF THE 4.5" TO APPROX 595'. THEY PULLED 1 JOINT. W&W CIRCULATED CEMENT FROM 575' TO SURFACE. KW PULLED TUBING, AND W & W TOPPED OFF WELL WITH CEMENT. WE FINISHED AT 10:30 AM AND USED APPROX 55 SXS OF COMMON. RIGGED DOWN AND MOVED TO HATCHER #1. 8/12 WHILE KW WAS DIGGING OUT AND CUTTING OFF WELL HEAD. JIM FOUND THE TOP OF THE SURFACE CASING. AFTER KW FINISHED THE HATCHER #1 MOVED BACK ON TO DAVIS TRUST #1 AND CIRCULATED 15 SXS OF COMMON DOWN THE BACKSIDE. THEY FINISHED AT 3:30 PM.

Perfs:

Top	Bot	Thru	Comments
458	464	CSG	


RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 22 2009

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

CONSERVATION DIVISION  
WICHITA, KS

VJK