

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21631-00-00  
Spot: W2NENW Sec/Twnshp/Rge: 34-27S-20W  
660 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: MCFADDEN "A" Well #: 1-34  
County: KIOWA Total Vertical Depth: 4902 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	392		WITH 350 SX CMT
PROD	4.5	4901	3720	WITH 165 SX CMT

159.32

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2009 11:45 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4825' WITH 4 SX CMT. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2009 1:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4825' WITH 4 SX CMT. 1ST PLUG AT 1300' PUMP 15 SX GEL, SET WIPER PLUG THEN PUMP 100# HULLS & 50 SX CMT. 2ND PLUG AT 420' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4890	4895		MISSISSIPPIAN
4877	4885		MISSISSIPPIAN

RECEIVED  
NOV 25 2009  
KCC WICHITA

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

DATE 1-4-10  
INV. NO. 2010060647

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton  
PIRT, IT (TECHNICIAN)

RECEIVED  
NOV 17 2009

KCC DODGE CITY

FORM CP-2/3