

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23025-00-00

Spot: NWSENW

Sec/Twnshp/Rge: 11-25S-18E

3770 feet from S Section Line, 3911 feet from E Section Line

Lease Name: PARRISH

Well #: 1

County: ALLEN

Total Vertical Depth: 900 feet

Operator License No.: 32595

Op Name: MSG RESOURCES INC.

Address: 975 1400TH ST
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	
PROD	2.875	900	0	

35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/07/2008 8:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from: MIKE BROWN

Company: MSG RESOURCES, INC.

Phone: (620) 365-7247

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CSING TO APPROXIMATELY 900' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: NONE

Date/Time Plugging Completed: 11/07/2009 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTONSEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN. 30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

NOV 12 2009

CHANUTE, KS

CPT

INVOICED

DATE 1-4-10

INV. NO. 2010060648

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P Titel

(TECHNICIAN)