

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21770-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 22-23S-37W
740 feet from S Section Line, 540 feet from W Section Line
Lease Name: KISEL Well #: 1-1215-2
County: KEARNY Total Vertical Depth: 5050 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		
SURF	8.625	1688		WITH 725 SX CMT
PROD	4.5	5050	3580	WITH 100 SX CMT <u>164.13</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 150# HULLS & 20 SX CMT. PLUG AT 1720' WITH 50 SX CMT. PLUG AT 800' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2009 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150# HULLS & 20 SX CMT TO 4756'. DISPLACE WITH 69 BBLs MUD & PRESSURE TO 1000 SPI. 1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4940	4946		ST LOUIS
4752	4756		MORROW
4740	4746		MORROW

INVOICED

DATE 1-4-10
INV. NO. 2010060652

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 19 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

NOV - 4 2009

KCC DODGE CITY

Form OR 2/3