

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20603-00-00
Spot: NESENW Sec/Twnshp/Rge: 10-10S-26W
3675 feet from S Section Line, 3097 feet from E Section Line
Lease Name: FULLER Well #: 2
County: SHERIDAN Total Vertical Depth: 4381 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	284	0	w/200 sxs cmt
PROD	4.5	4379	0	w/125 sxs cmt <u>142.38</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2009 1:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: RANDALL PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2009 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 284' w/200 sxs cement.
4 1/2" production casing set at 4379' w/125 sxs cement.
Port collar was cemented - depth and amount of cement is unknown. TD 4381'.
11-12-2009 - Ran tubing to 3000' - pumped 225 sxs cement with 400# hulls.
Pulled tubing to 1500' - pumped 60 sxs cement with 100# hulls.
Cement to surface. Pulled tubing to surface.
Connected to production casing - pumped 16 sxs cement.
Connected to 8 5/8" surface casing - pumped 75 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3927	3930		
3915	3918		

INVOICED

DATE 1-4-10

INV NO 2010060655

Remarks: S.O.S. CEMENTING COMPANY-TICKET #405.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED

NOV 30 2009

KCC WICHITA

Form CP-2/3

NOV 17 2009

RAINS & WILLIAMSON OIL CO
435 PAGE COURT

10-10-26W
NE SE NW

#2 FULLER

WICHITA, KS 67202

CONTR COMPANY TOOLS

CTY SHERIDAN

GEOL DAVE CALLAWAERT

FIELD FULLER CONF

E 2637 KB CM 6/11/81 CARD ISSUED 11/19/81 IP P 30 BO & 5 BWPD
LANS 3915-3918

+	+
+	+
+	+

API 15-179-20,603

LOG	TOPS	DEPTH	DATUM
ANH		2259	+ 378
TOP		3635	- 998
HEEB		3848	-1211
TOR		3871	-1234
LANS		3886	-1249
BKC		4118	-1481
CHER SH		4331	-1694
CHER LM		4337	-1700
RTD		4374	-1737
		4381	-1744

8 5/8" 284/200sx; 4 1/2" 4379/125sx

DST (1) 3884-3927/30-30-60-60, 690' GIP
450' GO, 180' HO & GCM, SIP 1142-
1142#, FP 44-109/142-262#

DST (2) 3948-3975/30-30-30-30, T'M
W/SPKS OIL, SIP 22-11, FP 11-11/
11-11#

DST (3) 4000-4044/30-30-30-30, REC 10'
OIL SPTD M, SIP 953-788#, FP 32-
32-32-32#

DST (4) 4039-4081/30-30-60-60, REC
80' SOCMW, SIP 1314-1292#, FP 54-
54/54-76#

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS