

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-19182-00-00  
Spot: SWSESESE Sec/Twnshp/Rge: 34-18S-4E  
326 feet from S Section Line, 628 feet from E Section Line  
Lease Name: UTTING Well #: 1  
County: MARION Total Vertical Depth: 2315 feet

Operator License No.: 5192  
Op Name: SHAWMAR OIL & GAS CO., INC.  
Address: 1116 E MAIN PO BOX 9  
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	200		UNKNOWN
PROD	5.5	2297		UNKNOWN <u>75.24</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2009 9:00 AM  
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.  
Proposal Rcvd. from: BENNY KEY Company: SHAWMAR OIL & GAS Phone: (620) 382-2932

Proposed Plugging Method: SAND TO 2247' AND CAP WITH 5 SXS CEMENT. CIRCULATE TO SURFACE FROM 250'.

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/28/2009 11:30 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2240' AND CAPPED WITH 5 SXS CEMENT. RAN TUBING TO 250' AND PUMPED 110 SXS TO CIRCULATE TO SURFACE. PLUG FELL 20' AND REQUIRED FIVE SXS CEMENT TO BRING TO SURFACE.

Perfs:

**INVOICED**  
DATE 1-4-10  
INV. NO. 2010060657

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 19 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: CONSOLIDATED WELL SERVICE TICKET #23742 TOTAL = 110 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

*PKT*

*JK*