

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21243-00-00
Spot: SENENWNW Sec/Twnshp/Rge: 24-33S-30W
600 feet from N Section Line, 1275 feet from W Section Line
Lease Name: SHINOGL Well #: 24-3
County: MEADE Total Vertical Depth: 2100 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1203		WITH 500 SX CMT
COND	20	40		

68.25

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 11/19/2009 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TIM THOMPSON Company: CROWN CONSULTING. Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2009 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

IST PLUG SURFACE CASING PARTED FROM 1203' TO 1270' (9/12/09). TIHWT TO 1750' & PUMP 125 SX CMT. WAIT ON CMT 24 HOURS. TAG PLUG AT 1300'. 2ND PLUG RIHWT (11/19/09) TO 623', LOADED HOLE WITH MUD THEN PUMPED 50 SX CMT. 3RD PLUG PULL TBG TO 312' & PUMPED 50 SX CMT. 4TH PLUG PULLED TBG TO 60' & PUMPED 20 SX CMT. CMT TO SURFACE.

Perfs: _____

INVOICED
DATE 1-4-10
INV. NO. 2010060661

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Jerry W. Stapleton
(TECHNICIAN)
PIRT II

RECEIVED
NOV 23 2009
KCC DODGE CITY

RECEIVED *PKT*
NOV 30 2009
KCC WICHITA