

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20467-00-00  
Spot: NWSW Sec/Twnshp/Rge: 25-27S-19W  
1980 feet from S Section Line, 660 feet from W Section Line  
Lease Name: END WRENCH Well #: 1  
County: KIOWA Total Vertical Depth: 4853 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N STE1010D  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	367		WITH 300 SX CMT
PROD	5.5	4852	2630	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2009 11:15 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4750' & 5 SX CMT. PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.  
157.72

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2009 12:35 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 4740' WITH 5 SX CMT. 1ST PLUG AT 1220' WITH 15 SX GEL, 100# HULLS & 50 SX CMT. 2ND PLUG AT 390' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4802	4804		
4798	4802		

**INVOICED**  
DATE 1-4-10  
INV. NO. 2010060662

Remarks: USED 60/40 POZMXI 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
NOV 23 2009  
KCC DODGE CITY

RECEIVED  
NOV 30 2009  
KCC WICHITA

Form CP-28

PKT