

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21115-00-00
Spot: NWSEENENW Sec/Twnshp/Rge: 35-27S-19W
750 feet from N Section Line, 1990 feet from W Section Line
Lease Name: ASHLEY Well #: 3-A
County: KIOWA Total Vertical Depth: 4890 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N STE1010D
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3492		
SURF	8.625	434		WITH 300 SX CMT
PROD	5.5	4886	2630	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/16/2009 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3380' & 5 SX CMT. PLUG AT 1270' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.
158.93

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2009 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 3380' WITH 5 SX CMT. 1ST PLUG AT 1270' WITH 15 SX GEL, WIPER PLUG, & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4832	4836		

INVOICED

DATE 1-4-10
INV. NO. 2010060662

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
NOV 23 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
(TECHNICIAN)
PART II

RECEIVED

NOV 30 2009

KCC WICHITA

Form 57-2/3