

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20767-00-01
Spot: NENENE Sec/Twnshp/Rge: 1-33S-18W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: CONRAD/MOORE Well #: 1-1
County: COMANCHE Total Vertical Depth: 5350 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
SURF	8.625	560		WITH 350 SX CMT
PROD	4.5	5327	2700	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2009 3:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 5000' & 2 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 60-0' WITH 20 SX CMT.

173.88

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2009 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5221	5226		MISSISSIPPI
5034	5045		PAWNEE

INVOICED
DATE 1-4-10
INV. NO. 2010060663

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
NOV 23 2009
KCC DODGE CITY

Signed Jerry W. Stapleton
(TECHNICIAN)
PART II

RECEIVED
NOV 30 2009
KCC WICHITA

PKT