

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-163-23,065-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Brito Oil Company, Inc. OPERATOR'S LICENSE NO. 4629

ADDRESS 200 E. First, Suite 208; Wichita, KS 67202 PHONE # (316) 263-8787  
175' S of

LEASE (FARM) Sutor WELL NO. 1-24 WELL LOCATION SE NW SW COUNTY Rooks

SEC. 24 TWP. 10S RGE. 20 ~~(E) (W)~~ TOTAL DEPTH 3758' PLUG BACK TD \_\_\_\_\_

**Check One:**

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 326' CEMENTED WITH 250 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 3745'-25 sx. 2nd  
plug at 1620'-25' sx. 3rd plug at 890'-100 sx. 4th plug at 350'-40 sx. 5th plug at 40'-10 sx

with wiper plug, Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 2 sx. Floseal.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No  
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 6:30 a.m. on 11-18-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton  
(Operator or Agent)

DATE: 12-15-89

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1989  
CONSERVATION DIVISION  
Wichita, Kansas