


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

GRAHAM County, Sec. 2 Twp. 10S Rge. 21W ~~XX~~ X (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner JOHN O. FARMER, INC.
Lease Name McCLELLAN Well No. # 2
Office Address Box 352, Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) OIL-SALT WATER DISPOSAL
Date well completed January 4 19 52
Application for plugging filed October 19 78
Application for plugging approved October 10 19 78
Plugging commenced November 3 19 78
Plugging completed November 3 19 78
Reason for abandonment of well or producing formation Well quit taking water

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3995 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	165	8-5/8"	165	None
		0	3805	5-1/2"	2805	None
				2-1/2"	cement lined tubing	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump in 100 sc. 50/50 Pozmix cement 5% gel in annulus between 8-5/8 and 5-1/2. Cement came out through tubing. Close tubing and pump cement down pipe @ 300#, final 200# standing pressure



Well Cemened by Allied Cementing Company

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor JOHN O. FARMER, INC.
Address Box 352, Russell, Kansas 67665

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
HAROLD A. CARLSON (employee of owner) or (XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Carlson
Box 352, Russell, Kansas 67665

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 78

Helen Carlson Notary Public.


My commission expires February 15, 1979

KANSAS DRILLERS LOG

S. 2 T. 10S R. 21W ^N_W

Loc. NW SW SE

County Graham County

640 Acres
N

Locate well correctly

Elev.: Gr.

DF 2246 KB 2248

API No. 15 — County — Number

Operator

JOHN O. FARMER, INC.

Address

Box 352, Russell, Kansas 67665

Well No.

2

Lease Name

McClellan

Footage Location

900

feet from ~~XXX~~ (S) line

330'

feet from ~~XX~~ (W) line

Principal Contractor

Jones, Shelburne & Farmer

Geologist

Gail Carpenter

Spud Date

2-8-51

Total Depth

3995'

P.B.T.D.

Date Completed

2-24-51

8-10-66 SWD

Oil Purchaser

Mobil Oil Company

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	165'	common	100 sx.	
Production	7-7/8"	5-1/2"	14#	3805'	common	100 sx.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-1/2" cement	lined 3800'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s) used as salt water disposal	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator JOHN O. FARMER, INC.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: SWD	
Well No. 2	Lease Name McClellan		
S <u>2</u> T <u>10</u> R <u>21</u> W ^{TE} _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Surface shale shells		700	
Shaleshells Anhydrite	700	1180	
Anhydrite Shale Shells	1270	2260	
Lime shale lime	2260	3485	
Lime lime shale	3485	3775	
Lime shale	3810		
Rotary T.D.	3810'		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Production Superintendent Title October 6, 1978 Date		