

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 24 Twp. 10S Rge. 20 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NW

Lease Owner Rock Island Oil & Refining Co., Inc.

Lease Name Sutor Well No. 3

Office Address 321 West Douglas, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 10/15 19 51

Application for plugging filed 6/11 19 68

Application for plugging approved 6/11 19 68

Plugging commenced 6/17 19 68

Plugging completed 6/17 19 68

Reason for abandonment of well or producing formation Oil production declined to economic limit

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey

Producing formation Arbuckle Depth to top 3752 Bottom Not Total Depth of Well 3755 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	184	-0-
				5 1/2"	3753	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well mudded from 3755' TD to 1200' from surface with 66 barrels of heavy rotary mud. A 100 sx. of 50-50 port cement was placed from 1200' to surface. Casing was cut off 4' below surface of ground and steel cap welded on top of cut-off casing.

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1968
CONSERVATION DIVISION
Wichita, Kansas



(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Rock Island Oil & Refining Co., Inc.
Address 321 West Douglas, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. D. Ables (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. D. Ables
321 West Douglas, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 19 68



Josephine Murphy
Notary Public.

My commission expires

OPERATOR Wood River Oil Company FARM NAME Sutor #3
 LOCATION SW NW NW Sec. 24-10-20W
 POOL NAME Berland COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE 10-6-51 COMPLETION DATE 10-15-51

LOG OF WELL

Elevation 2200 R. B.
 All Measurements from the top of rotary bushing.

FROM	DEPTH	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0		185			
185		715	Shale-Shells		
715		970	Shale-Sand		
970		1120	Shale	1000-00	
1120		1200	Sand		
1200		1300	Sand		
1300		1450	Shale-Shells		
1450		1620	Shale-Red Bed	1500-00	
1620		1640	Anhydrite		
1640		1667	Anhydrite		
1667		1860	Red Bed-Shale		
1860		1955	Lime-Shale		
1955		2175	Lime-Shale	2000-00	
2175		2300	Lime-Shale		
2300		2480	Lime-Shale		
2480		2585	Lime-Shale	2500-00	
2585		2710	Lime-Shale		
2710		2835	Lime-Shale		
2835		2890	Lime-Shale		
2890		2985	Lime-Shale		
2985		3100	Lime-Shale	3000-00	
3100		3215	Lime-Shale		
3215		3285	Lime-Shale		
3285		3350	Lime-Shale		
3350		3420	Lime-Shale		
3420		3470	Lime		
3470		3515	Lime	3500-00	
3515		3565	Lime		
3565		3601	Lime		
3601		3655	Lime		
3655		3708	Lime		
3708		3750	Lime-Shale		
3750		3755	T.D		

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 185.93 (6 Jts.) 8 5/8" O D Casing
 Ran 3756.56' (121 Jts.) 5 1/2" Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) SS

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C- G DRILLING CO.
 By RA Cook

Subscribed and sworn to before me this 17th day of October, 1951.

My commission expires: August 11, 1954

Abmeda Lowe
 Notary Public