

15-163-02187-0000

Form CP-1

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

P. O. BOX 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD


Locate well correctly on above Section Plat

Rooks County, Sec. 24 Twp. 10 Rge. 20 (E) (W)  
 Location as "NE/CNWSW2" or footage from lines NE SE NE  
 Lease Owner Southern States Oil Co.  
 Lease Name Sutor A#1 Well No. \_\_\_\_\_  
 Office Address Great Bend, Kansas 67530  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced 7/20/74 \_\_\_\_\_ 19\_\_\_\_  
 Plugging completed 7/26/74 \_\_\_\_\_ 19\_\_\_\_  
 Reason for abandonment of well or producing formation depleted.  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nassey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3760 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	248	none
				5 1/2"	3759	510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, sanded to 3740' and ran 5 sacks cement.  
 Shot pipe at 654', 593', 511', pulled 17 joints of 5 1/2" casing.  
 Allied pumped 2 sacks hulls, 20 sacks mud and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 19 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
 Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
 I, NOEL J. KNIGHT ss.


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS

Subscribed and Sworn to before me this 29th day of July 1974

My commission expires \_\_\_\_\_  
 MARGA  
 NOTARY PUBLIC  
 Rice County,  
 My Commission Expires  
 Feb. 15, 1975

Margaret Melcher  
 Notary Public.



MARGARET MELCHER  
 NOTARY PUBLIC  
 Rice County, Kansas  
 My Commission Expires  
 Feb. 15, 1975

15-163-02187-0000

COPY


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - BIRMINGHAM-BARTLETT DRG. CO.  
Farm - Sutor "A" No. 1

SEC. 24 T. 10 R. 20W  
NE SE NE

Total Depth. 3760' Corr.  
Comm. 3-14-49 Comp. 3-27-49  
Shot or Treated.  
Contractor. Birmingham-Bartlett Drlg. Co.  
Issued. 6-4-49

County. Rooks  
KANSAS



CASING:  
8-5/8" 248' Cem. W/ 150 Sx.  
5-1/2" 3759' Cem. W/ 85 Sx.

Elevation. \_\_\_\_\_

Production. 518 bbls.

Figures Indicate Bottom of Formations.

sand & clay	20
shale	120
shale & sand	248
shale & shells	1105
sand	1290
sand & shale	1505
shale & shells	1609
anhydrite	1638
shale & shells	2540
lime & shale	3240
lime	3415
shale & lime	3445
lime	3690
lime, shale & chert	3705
shale & lime	3760
chert	3762
arbuckle lime	3763
Total Depth	
Corrected T. D.	3760'
Tops:	
Heebner	3413
Lansing	3450
Sooy Conglomerate	3688
Arbuckle Dolomite	3759

RECEIVED  
STATE CORPORATION COMMISSION

JAN 25 1974

CONSERVATION DIVISION  
Wichita, Kansas