


15-163-02348-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

File All Information Completely
State Required Affidavit
Attest Before Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 24 Twp. 10 Rge. 20 (E) (W)
Location as "NE/CNW/SE/SW" or footage from line NE SW NE
Lease Owner Southern States Oil Co.
Lease Name Sutor A#5 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/25/74 19
Plugging completed 7/26/74 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	183	none
				5 1/2"	3757	481

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 3600' and ran 5 sacks cement.
Shot pipe at 851', 765', 677', 588', 484', pulled 17 joints.
Allied pumped 2 sacks hulls, 20 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

Subscribed and Sworn to before me this 31st day of July 1974

Margaret Melcher
Notary Public.



15-163-02348-0000

SUTOR "A" NO. 5

LOCATION: NE $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 24-10-20W
Rocks County, Kansas

OPERATOR: Birmingham-Bartlett Drilling Co.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 6 jts. 183.41' of 8-5/8", 24# casing cemented with 125 sacks cement and 1 CC.

OIL STRING: Ran 124 joints, 3763.59' 5-1/2" 15.50# J-55, 8 rd. thd. casing cemented with 100 sacks cement.

DATE SPUDDED: 11-20-49
DATE COMPLETED: 11-30-49

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1974
CONSERVATION DIVISION
Wichita, Kansas

L O G

(Figures indicate bottom of formation)

0 to	161	Sand and shale	3225	Shale
	840	Shale and shells	3295	Shale and lime
	1080	Sand and shale	3685	Lime
	1200	Sand	3705	Conglomerate
	1380	Shale	3745	Conglomerate chert
	1608	Shale and red bed	3755	Conglomerate
	1635	Anhydrite	3756	Shale
	2100	Shale and shells	3759	Arbuckle lime
	2280	Shale		
	2415	Shale and lime	3759	TOTAL DEPTH
	2555	Lime		
	2600	Lime and shale		
	3080	Shale		
	3115	Lime and shale		

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Sutor "A" No. 5 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me
this 2nd day of December, 1949.

Vivian L. Ginger
Notary Public

My commission expires November 29, 1950.