

15-163-02349-0000

Form CP-1

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
State Required Address  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217


Locate well correctly on above  
Section Plat

Tooks \_\_\_\_\_ County, Sec. 24 Twp. 10 Rgc. 20 (E) \_\_\_\_\_ (W) \_\_\_\_\_  
 Location as "NE/CNW/SE/SW" or footage from lines SW SE NE  
 Lease Owner: Southern States Oil Co.  
 Lease Name: Sutor A#6 Well No. \_\_\_\_\_  
 Office Address: Great Bend, Kansas 67530  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced 7/24/74 \_\_\_\_\_ 19\_\_\_\_  
 Plugging completed 7/26/74 \_\_\_\_\_ 19\_\_\_\_  
 Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3790 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	187	none
				5 1/2"	3788 1/2	599'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, sanded to 3250' and ran 5 sacks cement.  
 Shot pipe at 785', 693', 600', pulled 19 joints of 5 1/2".  
 Allied pumped 2 sacks hulls, 20 sacks mud and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 19 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor: KNIGHT CASING PULLING CO., INC.  
 Address: CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE  
NOEL J. KNIGHT ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS

Subscribed and Sworn to before me this 31st day of July, 1974

(Address) \_\_\_\_\_  
Margaret Melcher  
 Notary Public.

My commission expires \_\_\_\_\_  
  
 MARGARET T. MELCHER  
 NOTARY PUBLIC  
 Rice County, Kansas  
 My Commission Expires  
 Feb. 15, 1975

SUTOR "A" NO. 6

LOCATION: SW $\frac{1}{4}$  SE $\frac{1}{4}$  NE $\frac{1}{4}$  Sec. 24-10S-20W  
Rocks County, Kansas

OPERATOR: Birmingham-Bartlett Drilling Co.

CONTRACTOR: Birmingham-Bartlett drilling Co.

SURFACE CASING: Ran 6 jts., 190.80' of 8-5/8" 24# casing cemented at 187' with 100 sacks cement and 2 c.c.

OIL STRING: Ran 120 jts., 3790' 5 $\frac{1}{2}$ " 14# 8 rd. thd. casing cemented at 3788 $\frac{1}{2}$ ' with 100 sacks cement.

SPUDDED: 12-4-49

COMPLETED: 12-15-49

L O G

(Figures indicate bottom of formation)

0	to	187	Surface shale
		1000	Shale and shells
		1095	Sand, shale & shells
		1310	Sand
		1335	Shale and sand
		1621	Shale and red bed
		1652	Anhydrite
		1670	Shale
		2125	Shale and shells
		2590	Lime and shale
		3080	Shale
		3140	Lime and shale
		3245	Shale and shells
		3290	Shale and lime
		3715	Lime
		3788	Conglomerate
		3790	Arbuckle
		3790	Total Depth.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 25 1974

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Sutor "A" No. 6 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY

*Richard Hindery*

Subscribed and sworn before me  
this 17th day of December, 1949.

*Thomas J. Finger*  
Notary Public

My commission expires November 29, 1950.