


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

BRAHAM County. Sec. 24 Twp. 10 Rge. 21 (E) (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE NE  
Lease Owner C-G DRILLING CO. Inc.  
Lease Name Holzhauser Lease Well No. 1  
Office Address 206 Union National Bank Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Nov. 17 19 50  
Application for plugging filed Nov. 17 19 50  
Application for plugging approved Nov. 17 19 50  
Plugging commenced Nov. 17 19 50  
Plugging completed Nov. 17 19 50  
Reason for abandonment of well or producing formation Too low structurally

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Kays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" (25lbs.)	242.94'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Filled with drilling mud to 240'. Drove plug to 237'  
Put in 15 sacks cement then pumped full of mud 35'  
from top of hole. Drove plug down to 35' then filled to  
top with (19) Ten sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1950  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to C-G Drilling Co. Inc.  
Address 206 Union National Bank Bldg.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. A. Cook (~~Employee of Owner~~) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) R A Cook  
206 Union National Bank Bldg.  
(Address)

SUBSCRIBED AND SWORN to before me this 18 th day of November, 19 50.  
My commission expires June 25, 1951  
Wicky Fritz  
Notary Public.

PLUGGING  
FILE SEC 24 T 10 R 21 W  
BOOK PAGE 244 LINE 2



15-065-00180-0000

CONTRACTOR'S WELL LOG

Operator C-G Drilling Co. Inc. Farm Name Holzauer #1

Location SE SE NE sec.24-10-21W

Pool Name W. C. County Graham Co. State Kansas

Commencement Date 11-5-1950 Completion Date 11-17-50

LOG OF WELL

Elevation 2267 D, F.  
All Measurements from the top of rotary bushing.

DEPTH		FORMATION	DEVIATION FROM VERTICAL	REMARKS:
FROM	TO			
0	240			
240	725	Shale	0° - 500'	
725	780	Sand		
780	1030	Shale&Shells	0° - 1000'	
1030	1215	Shale&Shells		
1215	1425	Sand		
1425	1525	Shale&Shells	0° - 1500'	
1525	1680	Redbed&Sand		
1680	1737	Rebed&Shale		
1737	1774	Anhydrite	0° - 1750'	
1774	2055	Shale&Shells		
2055	2265	Lime&Shale	0° - 2250'	
2265	2365	Lime&Shale		
2365	2455	Lime&Shale		
2455	2565	Lime&Shale		
2565	2600	Lime&Shale		
2600	2700	Lime&Shale		
2700	2810	Lime&Shale	0° - 2750'	
2810	2920	Shale&Lime		
2920	3030	Lime&Shale		
3030	3125	Lime&Shale		
3125	3225	Lime&Shale		
3225	3310	Lime&Shale	0° - 3250'	
3310	3410	Lime		
3410	3465	Lime		
3465	3509	Lime		
3509	3555	Lime&Shale		
3555	3590	Lime		
3590	3645	Lime		
3645	3695	Lime		
3695	3720	Lime		
3720	3785	Lime		
3785	3835	Lime&Shale		
3835	3888	Lime&Shale		

RECEIVED  
REGISTRATION COMMISSION  
NOV 21 1950  
REGISTRATION DIVISION  
Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 242.94' ( 8 jts.) 8 5/8" OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) SS

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

PLUGGING  
FILE SEC-24-10-21W  
BOOK PAGE 44 LINE 8

C-G DRILLING CO. Inc.

By R. A. Park  
President

Subscribed and sworn to before me this 18th day of November, 1950

My commission expires:  
August 11, 1954

Abner Lowe  
Notary Public

