

15-065-02423-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 35 Twp. 10 Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 NE 21

Lease Owner Harry Gore

Lease Name Lewis Well No. 1 "A"

Office Address 400 Brown Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-11 19 53

Application for plugging filed 5-11 19 53

Application for plugging approved 5-11 19 53

Plugging commenced 10:30AM 5-11 19 53

Plugging completed 1:00PM 5-11 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set one plug at 190' - cemented with 15 sacks cement + mudded up to 40' - set plug 1/2 sack hulls - 10 sacks cement. Cemented to cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Veeder Supply & Development Company

Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas COUNTY OF Montgomery ss

Floyd W. Hild (employee of owner) or (conservation agent) of the above-described well, being first duly sworn, on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd W. Hild

Cherryvale, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1953

My commission expires July 11, 1956

John Lawson Notary Public


24-2675-S 2-52-20M

PLUGGING
FILE SEC T R
BOOK PAGE LINE

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1953
CONSERVATION DIVISION
Wichita, Kansas

15-065-02423-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm Lewis No. 1 "A" Depth 3775'
 Contractor Veeder Supply & Development Co. Pipe Set 203' of 8 5/8" casing
Cemented with 130 sacks cement
 Location NE 1/4 Sec. 35 Twp. 10 Range 21
 Commenced 4-29-53 Completed 5-11-53 County Graham State Kansas

Soil clay shale	0	40	40	Tops:	
Sand gray shale	40	150	110	Topeka	3146
Blue shale	150	203	53	Heebner	3151
Shale	203	525	322	Toronto	3377
Sand shale	525	600	75	Lansing KC	3396
Shale shells	600	1060	460	Base KC	3623
Sand	1060	1300	240	Cherty Conglomerate	3684
Shale	1300	1335	35	Weathered Arbuckle	3710
Shale shells	1335	1570	235	Solid Arbuckle	3743
Anhydrite	1570	1615	45		
Shale shells	1615	2030	415		
Lime shale shells	2030	2375	345		
Lime shale	2375	2610	235		
Lime shale shells	2610	3145	535		
Lime shale	3145	3435	290		
Lime	3435	3650	215		
Lime shale	3650	3714	64		
Cherty conglomerate	3714	3722	8		
Lime	3722	3775	53		
Total Depth	3775'				

Plugged @ 190' with 15 sacks cement.
 Plugged @ 40' with 10 sacks cement.

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being first duly and solemnly sworn on oath, says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state that the above drilling log covering the Lewis 1"A" well located in Section 35-10-21, Graham County, Kansas, is true and correct. Further affiant saith not.

Floyd W. Hild
 Floyd W. Hild

Subscribed and sworn to before me this 14th day of May, 1953.

Les Dawson
 Notary Public

My commission expires: July 11, 1956.

RECEIVED
 STATE OF KANSAS

COMMISSION EXPIRES
 July 11, 1956

PLUGGING
 FILE SEC 35-10-21-14
 BOOK PAGE 101 LINE 25