

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-24239-00-00  
Spot: N2N2NE Sec/Twnshp/Rge: 23-33S-5E  
330 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: ANDES Well #: 1  
County: COWLEY Total Vertical Depth: 1161 feet

Operator License No.: 6875  
Op Name: MARMIK OIL COMPANY  
Address: 200 N JEFFERSON STE 500  
EL DORADO, AR 71730

| String | Size  | Depth (ft) | Pulled (ft) | Comments    |
|--------|-------|------------|-------------|-------------|
| SURF   | 8.625 | 203        |             | 115 SX CMT. |
| T1     | 2.375 | 3008       |             |             |
| PROD   | 4.5   | 3066       |             | 100 SX CMT. |

37.73

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2009 8:00 AM  
Plug Co. License No.: 30492 Plug Co. Name: NICHOLS WELL PULLING SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2009 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @2,965', DUMP BAILED 4 SXS CEMENT ON TOP. PRESSURED CASING @ 250#, HELD OK. PERFORATED SQUEEZE HOLES @ 300'-301'. SWEDGED INTO 4-1/2" CASING CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, AND MIXED AND PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:00 PM., 11-6-2009. CONSOLIDATED CEMENT TICKET #23722.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3014 | 3022 | CSG  |          |

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 10 2009  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

Remarks:

Plugged through: TBG

DATE 1-12-10  
INV. NO. 2010060701

District: 02

Signed Duane Krueger  
(TECHNICIAN)