

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21975-00-00
Spot: SESESE Sec/Twnshp/Rge: 28-30S-9W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: WERNER Well #: 1-28
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LLC
Address: 15603 KUYKENDAHL STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4373		
CIBP		4376		
CIBP		4401		
SURF	8.625	259		225 SX
PROD	4.5	4498	3032	195 SX

146.25

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2009 8:00 AM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4285 AND CAP WITH 2 SKS, REC PIPE, 35 SKS 1450', 35 SKS 1000, CIRC 310-0', CIBP'S SET 4401, 4376', 4373'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 10/30/2009 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4250', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3032 AND PULLED TO 1470', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 1000', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 310', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4462	4466	CSG	
4403	4410	CSG	
4379	4390	CSG	
4351	4358	CSG	
4347	4349	CSG	
4337	4340	CSG	

INVOICED

DATE 1-12-10

INV. NO. 2010060705

RECEIVED

DEC 03 2009

Remarks: ALLIED CMTG #42999

Plugged through: CSG

KCC WICHITA

District: 02

Signed _____

(TECHNICIAN)

JK

PRT