

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21968-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 25-30S-9W
2970 feet from S Section Line, 2180 feet from E Section Line
Lease Name: DEPENBUSCH Well #: 1-25
County: KINGMAN Total Vertical Depth: 4497 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LLC
Address: 15603 KUYKENDAHL STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4436		
SURF	8.625	269		300 SX
T1	2.375	4422		146.15
PROD	4.5	4497	2903	195 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2009 12:00 PM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND PERFS TO 4275 AND CAP WITH 2 SKS OF CMT. RECOVER CASING, SPOT 35 SKS 1400', 35 SKS 950', AND CIRC CMT FROM 350-0'.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 11/03/2009 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4275', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2903', AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4392	4394	CSG	
4379	4384	CSG	
4359	4364	CSG	
4327	4343	CSG	

INVOICED
DATE 1-12-10
INV. NO. 2010060705

RECEIVED
DEC 03 2009
KCC WICHITA

Remarks: ALLIED CMTG 60/40 4% GEL #043000
Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)