

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24723-00-00
Spot: N2NESE Sec/Twnshp/Rge: 11-20S-11W
2310 feet from S Section Line, 825 feet from E Section Line
Lease Name: PANNING Well #: 1
County: BARTON Total Vertical Depth: 3550 feet

Operator License No.: 32325
Op Name: POPP OPERATING, INC.
Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	505	0	w/unknown sxs cmt
PROD	5.5	3375	2240	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2009 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING, INC. Phone: (620) 786-5514

Proposed
Plugging
Method:

Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

115.38

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2009 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded to 2760' - topped with 5 sxs cement.
Cut casing at 2240' - pulled casing to 1400' - tied onto casing and pumped 150 sxs cement with 300# hulls.
Pulled casing to 550' - pumped 60 sxs cement with 100# hulls.
Pulled casing to 200' - circulated cement to surface with 55 sxs cement.
Pulled casing - hole stayed full.

INVOICED
DATE 1-12-10
INV. NO. 2010060707

Remarks: QUALITY OIL WELL CEMENTING-TICKET #3883.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

RECEIVED

DEC 04 2009

KCC WICHITA

Form CP-2/3

CM

PRT

NOV 24 2009