

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23373-00-00

Spot: NWNWSE

Sec/Twnshp/Rge: 36-15S-14W

2160 feet from S Section Line, 2310 feet from E Section Line

Lease Name: MICHAELIS A

Well #: 1

County: RUSSELL

Total Vertical Depth: 3400 feet

Operator License No.: 32325

Op Name: POPP OPERATING, INC.

Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	865	0	325 SX CMT.

T1 2.875 3270

PROD	5.5	3396	2310	125 SX CMT.
------	-----	------	------	-------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/04/2009 3:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVE FUNK

Company: POPP OPERATING, INC.

Phone: (785) 483-3854

Proposed Plugging Method: Ordered 290 sxs 60/40 pozmix - 4% gel - 500# hulls.

110.50

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 11/04/2009 5:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded back to 2928' and topped off with 5 sxs cement.
Pulled casing to 1500' - pumped 150 sxs cement with 300# hulls.
Pulled casing to 900' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 500' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 200' - pumped 45 sxs cement to circulate to surface.
POOH. Cellar stayed full.

Perfs:

Top	Bot	Thru	Comments
3306	3307		
3303	3304		
3158	3160		
3146	3150		
3104	3110		
3092	3095		
2938	2942		

INVOICED

DATE 1-12-10

INV. NO. 2010060707

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3881.

Plugged through: CSG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

DEC 04 2009

KCC WICHITA

NOV 30 2009

replacement card

POPP OPERATING
HOISINGTON KS 67544

36-15S-14W
150'S, C NW NW SE

#1 MICHAELIS A

site 4 N & 3-1/4 E OF MILLARD KS

dy: RUSSELL

API 15-167-23373

contr: DISCOVERY DRILLING #2

field TRAPP

ged: ROBERT T. STOLZLE


fr
date 07/19/2006

spd
date 08/02/2006

drig
comp 08/08/2006

card
issued 02/26/2007

last
revised 03/26/2006



ELV: 1880 KB, 1872 GL LOG

tops.....depth/datum
TARK.....2558 -678
TOP.....2768 -888
PLATTSM.....2915 -1035
LANS.....3066 -1186
LANS C.....3092 -1212
ARB.....3300 -1420
PBTD.....3353 -1473
RTD.....3400 -1520

IP status

OIL, P 3 BO & 140 BWPD, SHAW 2938-2942 , LKC
3092-3160 OA , 10/09/2006

CORR & INFO REL: 3/26/2006 - CORR ELEV (WAS 1885 GL)
& PAY; WAS OIL WELL - TIGHT HOLE

CSG: 8-5/8" 865 / 325 SX (ALT 1), 5-1/2" 3396 / 125 SX

COMMENT: PROPOSED START 7/26/2006

NO CORES OR DSTS

TRGT ZN: ARB (OIL), PTD 3400 (ARB), MICT (9/8/2006) - CO,
PB 3353, PF (ARB) 3303-3304, W / 4 SPF, AC 500 GAL (7.5%),
SWB LD, RE-PF (ARB) 3305.5-3306.5, W / 4 SPF, RE-AC 250
GAL (7.5%), SWB LD, NON-COMMERCIAL, SET CIBP AT
3280, PF (PLATTSM) 2938-2942, (LKC) 3092,3095, 3104-3110,
3146-3150, 3158-3160, W / 4 SPF, AC 6000 GAL (15%), SWB
LD, SO, SET 2-7/8" TBG AT 3270, NO PKR, POP, IPP 3 BO &
140 BWPD, GTSTM (GR 36), DOFP 10/9/2006, COMMINGLED

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

100-25