

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20778-00-00  
Spot: NESWNWNE Sec/Twnshp/Rge: 34-25S-16W  
4575 feet from S Section Line, 2210 feet from E Section Line  
Lease Name: GIBSON Well #: 1-A  
County: EDWARDS Total Vertical Depth: 4427 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4415		
SURF	8.625	430		WITH 380 SX CMT
PROD	4.5	4427	1844	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2009 3:30 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: SAND TO 3925' & 4 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 470' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.  
143.88

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2009 6:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

DROPPED 350 GALLONS OF SAND. COULD NEVER GET ANY TOOLS PAST 1900'.  
PRESSURED TESTED CASING TO 200 PSIG. 1ST PLUG AT 1840' WITH 10 SX GEL &  
25 SX CMT. 2ND PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG AT 472'  
WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4034	4038		
3974	3976		

RECEIVED  
DEC 07 2009  
KCC WICHITA

INVOICED  
DATE 1-12-10  
INV. NO. 2010060708

RECEIVED  
DEC 07 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY CEMENTING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
NOV 23 2009  
KCC DODGE CITY

Form CS-273