

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22361-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 13-14S-22W
2310 feet from S Section Line, 4043 feet from E Section Line
Lease Name: SEIBEL D Well #: 1
County: TREGO Total Vertical Depth: 4195 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	160 SX CMT.
T1	2.375	4111		
PC		1663		
PROD	5.5	4188	0	100 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2009 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 120# hulls - 12 sxs gel (100#).
Port collar at 1663'.
136.34

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2009 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4096' - pumped 14 sxs gel - followed with 50 sxs cement.
Pulled tubing to 1663' - pumped 180 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - pumped 5 sxs cement.
Max. P.S.I. 175#. Shut in.
Filled 5 1/2" down - topped with 20 sxs cement - tube was full.

Perfs:

Top	Bot	Thru	Comments
4095	4098		
4090	4093		
4000	4095		

INVOICED
DATE 1-12-10
INV. NO. 2010060711

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3890.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN) CM

RECEIVED

DEC 04 2009 Form CP-2/3

NOV 30 2009

KCC WICHITA

Replacement Card

R P NIXON OPERATIONS
HAYS KS 67601-3898

13-14S-22W

83°W, C N/2 N/2 SW

#1 SEIBEL D

KANSAS

City: TREGO

Spot E2 NE NW SW API 15-195-22361

Site: 10-1/2 S & 1/2 E OF OGALLAH KS

Lat/Long: 38.83359 -99.72156

Field: MASSIER EAST

OIL

FR: 05/08/2006 Spd: 07/29/2006 Drig Cp: 08/05/2006 Issued: 10/16/2006 Revised: 10/20/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, P 6 BOPD & TR WTR, CHER 4090-4098 OA,
9/19/2006

Revisions: CORR & INFO REL: 10/20/2008 - CORR LTD
(WAS 4194); WAS OIL WELL - TIGHT HOLE

Notes: CORR 7/27/2006 - CONTR CHGD IN ERROR TO
SOUTHWIND DRILLING 6/29/2006

Contr: SHIELDS DRILLING #1

Geol: DAN A. NIXON

Elev: 2243 KB, 2238 GL, 2241 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

D ANH	1640 +603
D B/ANH	1688 +555
L TOP	3351 -1108
L HEEB	3596 -1353
L TOR	3618 -1375
L LANS	3633 -1390
L BKC	3878 -1635
L PAW	3975 -1732

L LABETTE	4024 -1781
L CHER SH	4051 -1808
L CHER SD	4070 -1827
L CHER SD-2	4090 -1847
L CONG	4104 -1861
L MISS	4132 -1889
PBT	4138 -1895
LTD	4195 -1952
RTD	4195 -1952

Csg: 8-5/8" 218 / 160 SX (ALT 2), 5-1/2" 4188 / 100 SX,
PORT COLLAR AT 1663

Finds:

COMMENT: PROPOSED START 7/5/2006; MI &
RURT 7/28/2006
SHOWS: 3670-3672 (LKC LM, TITE, MSTLY
BARREN, SLI TR V RR SPTY STN, NSFO, CALC
8% PORO), 4070-4072 (CHER SD, V FNE GRN,
WELL SRD, SUBRND, FRSTY, GRY W/LM
MTRX, MSTLY BARREN TITE, TR RR SPTY STN,
NSFO, CALC V TITE PORO), 4090-4100 (CHER