

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-01162-00-00

Spot: NWNWSE

Sec/Twnshp/Rge: 29-18S-11W

2310 feet from S Section Line, 2310 feet from E Section Line

Lease Name: FEIST B

Well #: 1

County: BARTON

Total Vertical Depth: 3487 feet

Operator License No.: 30458

Op Name: RJM COMPANY

Address: PO BOX 256

CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252	0	w/unknown sxs cmt
PROD	4.5	3485	0	w/unknown sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/05/2009 1:00 PM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: CHRIS HOFFMAN

Company: RJM COMPANY

Phone: (620) 587-3600

Proposed
Plugging
Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 350# hulls.
Emergency plug with rig over the hole.
Junk in the hole at 1200'.

113.33

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/05/2009 7:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 1125' - pumped 250 sxs cement with 350# hulls.
Pulled tubing - had circulation to surface and out backside. - called for more cement.
Tied onto casing - pumped 140 sxs cement - had 450# P.S.I. Shut in.
Tied onto backside - pumped 35 sxs cement - shut in at 500# P.S.I.

INVOICED

DATE 1-12-10
INV. NO. 2010060714

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

RECEIVED

DEC 04 2009 Form CP-2/3

KCC WICHITA

NOV 24 2009

PETROLEUM, INC

#B-1 FEIST

29-18-11W 53

NW NW SE

Contr. GARVEY DRLG

BARTON County

E 1837RB Comm.

Comp. 8-1-58

IP

98 BOPD, 2% WTR

Tops	Depth	Datum
ANH	645	1192
HEFB	2983	-1146
TOR	3000	-1163
DOUG	3015	-1178
BR IM	3098	-1261
LANE	3115	-1278
ARB	3449	-1612
TD	3487	-1650

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 252

= 4" 3485

DST 3137-60/1 HR, G/3", 2025' GSY O, BHP 940#

DST 3157-85/1 HR, G/50", 35' H O & GCM, 60' FR O, 30' GSY O, BHP 780#

DST 3243-85/1 HR, G/60", 122' H GCM, 61' H O & GCM, 61' MDY O, 649' GSY O, BHP 1000#

DST 3287-3305/1 HR, 45' MDY SW, BHP 940#

DST 3312-50/1 HR, G/35", 850' GSY O, BHP 940#

DST 3347-80/1 HR, 5' M, BHP 0#

SI PETER NW POOL DST 3366-3435/1 HR, 25' M, BHP 100#; DST 3454-

57/1 HR, 5' M, BHP 420#

12/3319-25: 10/3252-57:

A/1250: FLO 9 BFPH, 3% W:

24/3205-11: A/500: FLO 30

BFPH, 6% WTR

113.33